

ADDENDUM #4

Owner:
Montana State University
Facilities Management
Owner Rep: Donny Beebe
Project Manager, PDC

Architect:
Architects Alaska, Incorporated
347 S Ferguson Ave, Suite 3
Bozeman, Montana 59718
Project Architect: Thomas Brown

NOTICE TO BIDDERS

This Addendum is issued pursuant to the Instructions to Bidders. This Addendum serves to clarify, revise, and supersede information in the Contract Documents and previously issued Addenda. Portions of the Addendum affecting the Contract Documents will be incorporated into the Contract by enumeration of the Addendum in the Owner/Contractor Agreement.

The Bidder shall acknowledge receipt of this Addendum on the Bid Form.

The Date for receipt of bids is unchanged.

BIDDER QUESTIONS

Question 1 **Suppliers are telling me that pressure treated PSL posts don't exist. Are the posts supposed to be embedded into concrete?**

Answer 1 The PSL posts can be substituted with pressure treated glulam 5-1/2"x9-1/2" posts. The posts need to be embedded into the concrete sonotubes. Simkins Haulin confirmed these treated GL posts are available to order with couple weeks for shipping.

Question 2 **What are the existing truss heel heights? Is the truss 15 psf the dead load or top load?**

Answer 2 The heel heights are close to 6", field verify before procurement. The truss loading 15 psf is the dead load which breaks down to 10 psf will be for the top chord and 5 psf for the bottom chord.

ATTACHMENTS

NONE

END OF ADDENDUM